



**RAYTOWN  
QUALITY  
SCHOOLS**  
Expect the Exceptional

5911 Blue Ridge Blvd • Raytown, MO 64133 • Phone (816) 268-7160 •

**Mr. Josh Hustad**  
**Raytown School District**  
Josh.hustad@raytownschools.org

2023 Concrete Work Bid Tab

Contractor	Price
Legacy Underground Construction	39,683.00
FCC	43,825.00

I recommend that the Board of Education approve Legacy Underground Construction to complete the 2023 Concrete Work in the amount not to exceed \$39,683.00.



March 20<sup>th</sup>, 2023

Attn: Josh Hustad  
Raytown School District

RE: Raytown Concrete 2023

Legacy Underground Construction, Inc is pleased to present to you our proposal for the above-mentioned project. Addendum 1 has been acknowledged.

**Price: \$39,683.00**

**Raytown Administration Bldg.: \$4988.00**

- Provide and install 25'x8' of sidewalk w/ handicap entrance.
- Provide and install 17'x7' of sidewalk w/ handicap entrance.
- Provide haul off of debris.
- Provide and install wire mesh mats.
- Provide safety barriers.
- Provide saw cutting.
- Provide seed /mulch of disturbed area.
- Provide layout.

**Raytown Education Conference Center: \$9665.00**

- Provide and install 20'x16' pad 4" thick w/ 4" gravel.
- Provide and install 20'x23' pad 4" thick w/ 4" gravel.
- Provide haul off of debris.

- Provide and install wire mesh mats.
- Provide safety barriers.
- Provide seed /mulch of disturbed area.
- Provide saw cutting.
- Provide layout.

**RSECC: \$10,150.00**

- Provide and install 16'x50' Entrance w/ 2-4' ADA Mats.
- Provide haul off of debris.
- Provide and install wire mesh mats.
- Provide safety barriers.
- Provide seed /mulch of disturbed area.
- Provide saw cutting.
- Provide layout.

**Wellness Center: \$14,880.00**

- Provide and install 22'x23' of Entrance
- Provide and install 31'x9' of Sidewalk w/ 2-4' ADA Mats.
- Provide and install 12'x8' of sidewalk.
- Provide and install 33' of curbing.
- Provide haul off of debris.
- Provide and install wire mesh mats.
- Provide safety barriers.
- Provide seed /mulch of disturbed area.
- Provide saw cutting.
- Provide layout.

**Price excludes:** Permits, Bonds, and Engineering

Thank You for the opportunity to bid this project. If there are any further questions or information needed, please feel free to call me at 816-558-5162

Thank You,

*David Scaggs*  
President



**652013 Raytown SD Concrete Work  
(2023) - Raytown, MO**

**03/20/2023**

---

## Scope

Base Bid:

### Raytown Administration Building:

- Remove Existing 4" Concrete Sidewalk and Dispose of Spoils (approximately 320 SF)
- Install 4" Concrete Sidewalk with #4 Rebar @ 24" OC and ADA Detectable Warning Systems (2 EA) (approximately 320 SF)

### Education Conference Center:

- Excavate Existing Earth 8" and Dispose of Spoils in preparation for Concrete Installation (approximately 860 SF)
- Install 4" Concrete Pavement with #4 Rebar @ 24" OC and 4" of AB3 Base Rock (approximately 780 SF)
- Install 4" Concrete Sidewalk with #4 Rebar @ 24" OC and 4" of AB3 Base Rock (approximately 80 SF)

### Entrance at Wellness Center:

- Remove Existing 4" Concrete Pavement, Sidewalk, and Curb and Gutter and Dispose of Spoils (approximately 947 SF)
- Install Standard 12"x24" Concrete Curb and Gutter with No Reinforcement (approximately 33 LF)
- Install 4" Concrete Sidewalk with #4 Rebar @ 24" OC and ADA Detectable Warning Systems (2 EA) (approximately 375 SF)
- Install 4" Concrete Pavement with #4 Rebar @ 24" OC (approximately 506 SF)

### Entrance to RSECC

- Remove Existing 4" Concrete Pavement and Dispose of Spoils (approximately 800 SF)
- Install 4" Concrete Pavement with #4 Rebar @ 24" OC and ADA Detectable Warning Systems (2 EA) (approximately 800 SF)

**Base Bid Total: \$43,825.00**

---

Our PROPOSAL **EXCLUDES** THE FOLLOWING:

**If it's not qualified above, it's not included.** Engineering, Erosion Control, **ROCK EXCAVATION**, As-Built Drawings, Staking, Undercutting/Replacement of Unsuitable Soils, Soil Stabilization, Soil Additives, Topsoil, Amended Soils, Frost or mud removal, Spoils removal, Temp utilities, utility relocation, utility bills, lighting, toilets, and dumpsters, Site Utilities, Site